

Designing for Aquatic Organism Passage at Road-Stream Crossings







Stream Simulation: A Simple Example

Stillwell Creek

Finished Project -How did we do it?





Old culvert inlet

New culvert



Phase 1 Initial Assessment

Phase 6

Maintenance

& Monitoring

Phase 5

Construction

Stream
Simulation
Project
Phases

Phase 2
Site Assessment



/ Phase 3
Stream Simulation
Design

Phase 4
Final Design &
Contract Preparation



Phase 1 - Initial Assessment

- Primary Resource Objective is
 - to provide access for <u>salmon & coastal cutthroat</u>
 to 1 mile of valuable rearing and spawning habitat.
 - provide access for other aquatic organisms for aquatic ecosystem restoration.
- Secondary Resource Objective is
 - maintain vehicle access for watershed management

Example of Local Residents and Visitors

Coho salmon



steelhead



Coastal cutthroat trout



Crayfish




Pacific giant salamander



Tailed



sculpin



Initial Assessment of Watershed Characteristics & Risks

• Stability:

- Geology is weathered sandstone, mudstone and basalt.
- Landslide and debris torrent prone topography.
- Periodic input of large conifers and alders.
- Annual input of colluvium and wood debris

Looking upstream at Wood and sediment



Risk of culvert plugging, road embankment failure, "take"




Phase 2 - Site Assessment

- Develop Plan view sketch map
 - identify bank characteristics, stability, materials
 - geotechnical subsurface investigation
- Obtain survey site plan for stream restoration and structure design
 - Analyze long profile and alignment
 - Determine structure's channel position: grade, elevation, bearing, length
- Analyze and interpret site data
 - Identify a reference reach, channel design template
 - quantify & characterize bed, bank and grade control materials
- Results understand risks, detailed project objectives


Site Survey

Sharp skew angle, makes for a long structure

Both banks are steep and will control location of new culvert edges



Long Profile



Upstream Channel

Aggraded inlet.
Sediment wedge upstream



Upstream Debris torrent deposits & large wood, Periodic bedrock exposure



Downstream Channel

3' deep outlet pool scoured to bedrock.

Avg. depth to bedrock estimated to be 2 feet by observation & drive probe

Downstream wood grade controls, periodic bedrock exposure





Reference Reach Analyze and Interpret

- Similar to culvert location
 - gradient (3.8%)
 - Average bank full width (18 feet)
 - bed material sizes
 - soil and alluvium banks
 - Moderately formed steppools of cobbles and wood





Site Suitability Questions

- Given site conditions what structure types are feasible?
 - Is there bedrock within the desired embedment depth?
 - Channel restoration is needed to correct aggraded and scoured pool area.
- What are the long term risks?
 - Debris plugging and fill failure
- Structure Feasibility yes for all
 - ✓ Bridge skew?, largest opening
 - ✓ Open bottom arch good for bedrock
 - ✓ Embedded pipe 2 ft embedment depth?

Phase 3 -Stream Simulation Design

- Pick the appropriate structure for the site.
 - Determine structure width, length

Use the reference reach information, and identify:

- Desired stream width inside culvert
- Desired gradient
- Type of bedforms inside culvert
- Embedment depth of culvert


Identify alternative structures

- Results:
 - sketches and descriptions of stream simulation bed and depth for engineering design and contract
- Document design process & assumptions for contract administration and monitoring purposes

Stream Simulation Design, Structure Width

- Analyze various structure sizes and shapes that meet design width:
 - Check with FishXing ~ ½ full at Q100
 - Room for debris? ~ mostly, big trees = maintenance
 - How well does it fit? ~ ease of bed construction and stability features.
- Final choice: Choose 18' x 8'11" open bottom arch
 - Economical shape, large opening, embedment depth
 - With concrete footings formed on bedrock

Long Profile - Checked Against Alignment



Select bedform materials

- Best reference reach in recently deposited sediments.
- Developing steps
 composed of largest
 material.
- Construct steps within culvert @ reference reach spacing
- Important for stream material stability.



Stream Simulation Design Select Bed Material Gradations

- Stream simulation materials to give you similar
 - stability
 - permeability
 - Complexity
- "Pebble count" gradation of streambed
 - Is the same as an engineering gradation (% passing & sieve size)
- Construct steps with largest material
 - Individual rocks or graded material

Phase 4 - Final Design and Contract Preparation


- Produce drawings and specifications for:
 - structure and foundation details, bedding
 - roadway,
 - erosion control, dewatering,
 - bypass roads,
 - stockpile sites.
 - and everything else
- Determine quantities and estimate costs
- Develop Contract Documents
- Results: Final design and Contract solicitation package

Contract Drawings follow for:


- Site Plan
- Structure Profile
- Structure Cross Section
- Dewatering Plan

New Structure Alignment


Headwalls considered to reduce length but were too costly for a noticeable improvement.



Site Plan, Profile, Survey




Stream Simulation Channel Shape



- CONSERVE ALDER LOGS (W/ STUMPS ATTACHED) FROM CLEARING OPERATION, PLACE IN SIMULATED STREAMBED AS DIRECTED BY CO.
- FILL VOIDS IN STREAM SIMULATION ROCK W SELECT BORROW COMPACT EACH LAYER AS PER SPS 251.02F1
- SQUIPMENT MAY CROSS STREAMBED DIRECTLY DOWNSTREAM
 OF ARCH PRIOR TO COMPLETION OF SIMULATED STREAMBED
- PLACE SANDBAG DAM DOWNSTREAM OF SCOUR-POOL AS NEEDED TO DEWATER POOL

Stream Channel Structure



Phase 5 - Construction

- Inspection and control
- Documentation
- Design changes (minimize)

Phase 5 - Construction



- Footing are constructed, steps built, and stream simulation materials placed
- Note: the streambed has been diverted into a pipe runs parallel to the footing.



Structure is assembled and backfilled

Completed Project



Completed Road Crossing for traffic


Completed Stream Crossing for Aquatic Organisms



Phase 6 - Post Construction Maintenance and Monitoring

- Monitor not intensive for this project
 - Biological monitor # reds developing
 - -Structure settlement, foundation scour
 - -Streambed stability, shape, complexity
 - -Site Stability bank erosion, stability


MIddle Stillwell 2003 thalweg profile



Prior to replacement.

Note the aggraded sediment wedge above the culvert and the plunge pool below it. Gradient of red line through culvert area is 3.85%.

Lower Stillwell thalweg profile 2006



Thalweg profile April 2006 after 3 winters.

Note the gradient is becoming more uniform along the red line.

Conclusions

Goals:

 Passage for aquatic organisms that are present, water (Q100 flow), and sediment.

Method:

 Connecting the stream channel above and below the culvert with a similar stream segment through the culvert or bridge.

RESULT:

Barrier to organisms wood and flow achieved, and risk to road greatly reduced.